

ducting express

Ducting Express Services Ltd
Unit 3 Claymill Rd, Thurmaston
Leicester, LE4 9JJ

The free air aperture of the RA roof terminals at point of exit from the base unit are as follows;

Mini Cowl = 0.0283

RA200/250 = 0.055 cu mt 2

RA300/315 = 0.089

RA350 = 0.114

RA400/450 = 0.190

RA500/560 = 0.274

RA630/710 = 0.460

RA800 = 0.640

RA1000 = 0.950

These figures are based upon the maximum cut height of the terminal upstand and so worse case scenario. In practice the units are trimmed slightly lower, which as they are tapered will give a slight increase in area available. Not a significant amount, but a useful margin for error.